

Clarence Central School District – 2019 Capital Project (DRAFT)

Item #	Bldg.	Description
1	HS	Reconfigure main entrance vestibule to provide increased security at building.
2	MS	Reconfigure main entrance vestibule to provide increased security at building.
3	CC	Install new addition at main entrance to provide increased security at building.
4	HH	Reconfigure main entrance vestibule to provide increased security at building.
5	LV	Install new addition at main entrance to provide increased security at building.
6	SH	Reconfigure main entrance vestibule to provide increased security at building.
7	HS	Install code required handicap locker benches at all locker rooms.
8	HS	Replace rolling shutter and man door behind stage with code required fire-rated rolling shutter and man door.
9	HS	Modify walls for code required handicap accessibility in miscellaneous toilet rooms.
10	HS	Replace existing Auditorium sound system, and install new sound system and assistive listening system.
11	HS	Replace existing Auditorium Air-handling unit.
12	HS	Replace (15) deteriorated roof top units (of the (31) total units) over than 15 years old. (includes new steel/asbestos and roofing).
13	HS	Replace flooring at miscellaneous rooms. (Replace carpeting with new carpet in District offices, Lecture Hall, Media Center and surrounding areas. Remove carpet and install new vinyl flooring in miscellaneous classrooms)
14	HS	Stop ground water infiltration in the basement generator room.
15	HS	Exterior masonry restoration: Includes repointing, rebuilding brick walls, etc.
16	HS	Install additional roof drain, rework south upper wall of Auditorium, reseal all parapet wall flashings at Gymnasium.
17	HS	Replace 1997 vintage built -up roof and thruwall flashing at main entrance, Cafeteria, Bridge and Music Suite areas.
18	HS	Renovate existing football locker room into building storage. Install new athletic team/locker room and storage room addition located at the end of the Math wing (rooms 449/450).
19	HS	Replace deteriorated drywall wall with new concrete block wall located in the Boy's and Girl's Pool locker rooms.
20	MS	Replace smoke detectors older than 10 years.
21	MS	Modify walls for code required handicap accessibility in miscellaneous toilet rooms.
22	MS	Replace carpet at Media Center. Replace flooring in miscellaneous areas including Main Office areas, and House office suites.
23	MS	Replace (5) deteriorated roof top units (of the (28) total units) (includes new steel/asbestos and roofing).
24	MS	Disconnect and remove existing acid sump/pump assembly. Remove existing acid neutralization tank. Provide new tank outside building and extend piping new piping thereto.
25	MS	Exterior masonry restoration: Includes repointing, rebuilding brick walls, etc.
26	MS	Install new thru-wall flashing at roof level around upper gym wall.
27	MS	Replace existing built up roof areas at the 1990's wings (North Gym, Cafeteria, and classroom wing)
28	MS	Reconstruct existing loading dock and stairs located at Kitchen.
29	CC	Replace original main entrance exterior stairs at 1939 building.
30	CC	Replace roof at Kindergarten wing, original building and 1955 wing.
31	CC	Move existing kitchen serving line to allow for code required handicap clearances.
32	CC	Replace flooring in Faculty bathroom, Library break room and all Kindergarten room bathrooms with new flooring.
33	HH	Provide transfer grilles with smoke and fire dampers in Kitchen/Cafeteria wall.
34	HH	Replace floor expansion joints at corridors.
35	HH	Replace flooring in Main Office Area, Media Center and miscellaneous rooms.
36	HH	Exterior masonry restoration: Includes repointing, rebuilding brick walls, etc.

Item #	Bldg.	Description
37	HH	Replace flooring in Boy's and Girl's locker room and Boy's and Girl's toilet rooms 202/204 with new flooring.
38	HH	Miscellaneous Asbestos abatement
39	LV	Miscellaneous masonry restoration allowance. (repainting, rebuilding brick walls, etc.) (Raymond E. Kelley to evaluate after vote)
40	LV	Replace carpeting in Media Center (including adjacent offices)
41	LV	Replace deteriorated ceramic wall tile and ceiling in Kitchen and adjoining dish wash area.
42	LV	Replace nurse's office floor with new vinyl flooring.
43	SH	Replace existing water heaters with new code required rated water heaters.
44	SH	Provide transfer grilles with smoke and fire dampers in Kitchen/Cafeteria wall.
45	SH	Replace floor tile in (7) classrooms and 1/3rd of corridors (including abatement).
46	SH	Exterior masonry restoration: Includes repointing, rebuilding brick walls, etc.
47	SH	Replace flooring in Boy's and Girl's locker room and Boy's and Girl's toilet rooms 201/203 with new flooring.
48	BG	Replace carpet with vinyl flooring in the office area.
49	BG	Replace rear parking lot. (full depth excavation).
50	BG	Replace roof at Office area.
51	B&G	Exterior masonry restoration: Includes repointing, rebuilding brick walls, etc.
52	HS	Replace remaining south parking lot including subbase.
53	SH	Replace original site lighting poles. Lighting fixtures were replaced previously.
54	HS	Install storm water pump at well #6 located near storage building.
55	HS	Replace old acid neutralization tank serving 400 series science rooms. Clean, flush and replace limestone in acid neutralization tank serving 500 series science rooms.
56	MS	Replace interior fluorescent, incandescent and HID lighting w/ new LED lighting (Large group areas such as Cafeteria, LGI, Media Center, Pool).
57	MS	Repair courtyard foundation to eliminate water infiltration in basement storage room.
58	CC	Replace flooring in Kindergarten classrooms, corridors and 1955 classrooms and corridor. Includes abatement.
59	HH	Replace miscellaneous classroom and corridor floor tile (including abatement).
60	HH	Replace interior fluorescent, incandescent and HID lighting w/ new LED lighting (Large group areas such as Cafeteria and Media Center).
61	LV	Remove and replace all existing asbestos containing soffits around entire building.
62	LV	Replace ceilings at Nurses' Areas. (Lighting include in separate line item)
63	BG	Replace existing water heaters with new code required rated water heaters.
64	BG	Renovate existing toilet rooms for code required handicap accessibility.
65	HH	Replace existing Auditorium sound system, and install new sound system and assistive listening system.
66	SH	Replace floor expansion joints at corridors.
67	LV	Renovate Boy's and Girl's Gang Toilet rooms in 1950's wing.
68	SH	Replace flooring in Main Office Area, Media Center and adjacent rooms.
69	MS	Install new storage addition located off of south cafeteria.
70	CC	Install new storage addition located off of gymnasium.
71	HH	Install new storage addition located off of gymnasium.
72	LV	Install new storage addition locate adjacent to Kindergarten classrooms.
73	SH	Install new storage addition located off of rear custodial/ boiler room.
74	MS	Renovate storage area into new Team Locker room located in the basement.
75	MS	Replace (5) 1990's vintage air handling units.
76	HH	Replace existing cafeteria unit ventilators with new roof top units.
77	HH	Remove existing abandon sidewalk elevator located in basement and install new sidewalk at grade.
78	HS	Provide elevator sump pump with oil sensing capabilities.
79	HS	Replace all parking lot lighting with new LED lighting. (Light heads only, poles are new)
80	MS	Replace ceramic tile walls, treads and risers in stairway west of main gym.
81	MS	Replace remaining interior incandescent exit lights with new LED light fixtures.
82	HH	Replace deteriorated gymnasium wall pads.
83	LV	Replace existing asbestos flooring and install new vinyl flooring in all original classrooms.
84	SH	Replace existing freezer, cooler and dishwasher.

Item #	Bldg.	Description
85	CC	Replace Stage Theatrical Lighting System with new LED System.
86	HH	Replace Stage Theatrical Lighting System with new LED System.
87	LV	Replace Stage Theatrical Lighting System with new LED System.
88	SH	Replace Stage Theatrical Lighting System with new LED System.
89	HS	Provide new hardwired carbon monoxide detection system to replace existing battery operated units.
90	MS	Provide new hardwired carbon monoxide detection system to replace existing battery operated units.
91	CC	Provide new hardwired carbon monoxide detection system to replace existing battery operated units.
92	HH	Provide new hardwired carbon monoxide detection system to replace existing battery operated units.
93	LV	Provide new hardwired carbon monoxide detection system to replace existing battery operated units.
94	SH	Provide new hardwired carbon monoxide detection system to replace existing battery operated units.
95	BG	Provide new hardwired carbon monoxide detection system to replace existing battery operated units.
96	BG	Replace original infrared heaters located in the bus bays.
97	HS	Replace (4) A/C split systems located in miscellaneous student occupied spaces.
98	HS	Repair hot water recirculation lines that are pitting due to water turbulence. Rebalance system.
99	HS	Replace miscellaneous exterior doors including District Office curtain wall.
100	MS	Replace original 1966 site lighting in front of building with LED lighting.
101	MS	Replace all remaining site lighting with LED (Light heads only, replace heads on poles from 2005 project)
102	MS	Replace pavement and subbase at the front bus loop and parking lot. Reseal/stripe west lot and Bus loop/drive. Replace rear walk.
103	MS	Replace miscellaneous A/C split systems.
104	MS	Replace (18) unit ventilators in the 1994 addition.
105	CC	Replace several exterior doors and miscellaneous interior vestibule doors.
106	CC	Replace areas of deteriorated galvanized water piping.
107	CC	Replace existing gymnasium sound system, and install new sound system and assistive listening system.
108	HH	Replace miscellaneous deteriorated exterior doors.
109	HH	Install new split systems for offices and conference rooms.
110	HH	Install new dishwasher exhaust hood.
111	HH	Replace Gym windows.
112	LV	Replace deteriorated cooler/freezer.
113	LV	Replace existing cafeteria/gymnasium sound system, and install new sound system and assistive listening system.
114	LV	Replace all original building corridor doors. (Install electric hold opens as alternate bid)
115	SH	Replace sections of deteriorated sidewalks.
116	SH	Replace miscellaneous deteriorated exterior doors.
117	HS	Install Variable Frequency Drives (VFD's) and controls on pumps. Replace dishwasher booster heater.
118	MS	Install Variable Frequency Drives (VFD's) and controls on pumps. Install refrigeration controls
119	HH	Install Variable Frequency Drives (VFD's) and controls on pumps. Upgrade refrigeration controls.
120	SH	Install Variable Frequency Drives (VFD's) and controls on heating pumps.
121	SH	Replace existing gymnasium sound system, and install new sound system and assistive listening system.
122	SH	Replace Gym windows.
123	HH	Replace original site lighting poles/bases. Fixtures were replaced in previous project.
124	HS	Replace doors around rear of Auditorium and all 2nd floor corridor doors at original building.
125	HS	Replace lockers in science hallway adjacent to Lecture Hall.
126	HS	Replace basement sump pumps.
127	CC	Replace ceilings in 1970's classrooms.
128	BG	Re-grade culverts located at street and driveway.

Item #	Bldg.	Description
129	CC	Replace original single pane windows in 1970's classroom wing.
130	LV	Replace original single pane windows at original building (rescue windows are also against code) replace with new brick walls/ windows and perimeter casework.
131	LV	Replace interior fluorescent, incandescent and HID lighting w/ new LED lighting (Large group areas such as Media Center).
132	SH	Replace interior fluorescent, incandescent and HID lighting w/ new LED lighting (Large group areas such as Cafeteria and Media Center).
133	BG	Expand front parking lot for 12 additional cars.
134	HH	Replace deteriorated sidewalk in front of building.
135	HS	Clean all ductwork located in the building (not all areas have ductwork).
136	MS	Clean all ductwork located in the building (not all areas have ductwork).
137	CC	Clean all ductwork located in the building (not all areas have ductwork).
138	HH	Clean all ductwork located in the building (not all areas have ductwork).
139	LV	Clean all ductwork located in the building (not all areas have ductwork).
140	SH	Clean all ductwork located in the building (not all areas have ductwork).
141	BG	Clean all ductwork located in the building (not all areas have ductwork).
142	LV	Replace (2) existing original gymnasium folding partitions.
143	HS	Extend J.V. Baseball and J.V. Softball backstop fencing.
144	HS	Seal all cracks and seal entire west lot including alleyway behind school.
145	HS	Replace front parking lot and drop off including subbase.
146	CC	Replace front parking lot including subbase. Reseal/stripe rear parking lot.
147	HS	Replace gymnasium wall padding.
148	LV	Replace original site lighting poles. Fixtures were replaced.
149	HS	Replace J.V. Softball infield.
150	MS	Update energy management system. (Change existing N2 controllers on equipment to backnet controllers)
151	HH	Update energy management system. (Change existing N2 controllers on equipment to backnet controllers)
152	SH	Update energy management system. (Change existing N2 controllers on equipment to backnet controllers)
153	HS	Update energy management system. (Change existing N2 controllers on equipment to backnet controllers)
154	CC	Replace original plumbing fixtures (sinks, toilets and faucets) throughout entire building.
155	HH	Replace original plumbing fixtures (sinks, toilets and faucets) throughout entire building.
156	LV	Replace original plumbing fixtures (sinks, toilets and faucets) throughout entire building.
157	SH	Replace original plumbing fixtures (sinks, toilets and faucets) throughout entire building.
158	MS	Replace original single pane windows at original building (rescue windows are also against code).